ESTIMATE

Dr. Masonry – Mateo Fabricio Diaz Borja · 406 539 9290

Stone Floor Demolition & Re-Installation

Client: Tyler (YC)
Location: 7 South Cabin Road, American Spirit, Yellowstone Club, Big Sky, MT
Date: November 6, 2026
Valid for: 30 days
Project area: 530 sq ft natural stone floor

Scope of Work

1. Protect surrounding surfaces, walls, and fixtures.
2. Demolish and remove the existing stone floor, setting bed, and grout.
3. Prepare the base and build a new mortar bed with a proper slope, so water drains toward the opposite side of the room.
4. Install the natural stone, back-buttering each piece with thin-set mortar for full contact and adhesion.
5. Fill all joints between the stones.
6. Apply sealer (2 coats) over the entire floor.
7. Install epoxy at the perimeter of the area.
8. Final cleanup and removal of debris.

Materials Required (Provided by the Client)

All materials are to be purchased and paid for by the client. The following materials and quantities are required for the job:

Material	Specification	Quantity	Est. Cost
Mortar mix (Quikrete, red bag)	Mortar bed with slope for water drainage	25 bags	$250
Thin-set mortar (Laticrete)	Back-butter and set each stone	10 bags	$550
Sealer (J26WB)	2 coats over the entire floor	2 buckets	$800
Epoxy	Perimeter of the area	As required	$1,500
		Estimated materials total (paid by client)	**$3,100**

Result

With this work, the floor will have a proper slope so water drains toward the opposite side of the room, and the floor will be completely sealed against water.

Total Price

Total (labor only — materials not included) **$27,888**

Terms & Notes

- Estimated duration: 11 working days (3 days of demolition + 8 days of installation), with a crew of 4 masons, 8 hours per day.
- **We will make every effort to carefully remove and salvage the existing stone so it can be reused, avoiding the cost of purchasing new stone.**
- Materials are provided by the client and must be on site before work begins.
- Payment terms: 50% deposit to schedule, balance upon completion.
- Foot traffic should be limited for 24–72 hours after sealing.
- Work is scheduled for temperatures above 50 °F (10 °C) to ensure proper curing.

Question for the Client

Do you have a dumpster on site that we can use to dispose of the debris and trash from the demolition?

YC & Client Approval

Name: _____ **Phone / Email:** _____

Client signature: _____ **Date:** _____